

# PRELIMINARY STORMWATER MANAGEMENT REPORT

*FOR*


**THE SUBDIVISION**

at

6225 McLeod Lane NE

Keizer, OR.

January 19, 2024



**PREPARED BY:**

**7 OAKS ENGINEERING, INC.**

Kim Johnson, P.E.

345 Westfield St. #107

Silverton, Or. 97381

503.308.8554

[kim@7oaksengineering.com](mailto:kim@7oaksengineering.com)

Contents

I. PURPOSE OF REPORT..... 3  
II. PROJECT DESCRIPTION..... 3  
    A. EXISTING CONDITION..... 3  
    B. PROPOSED CONDITION..... 3  
III. METHODOLOGY ..... 4  
IV. CALCULATIONS ..... 6  
V. SUMMARY..... 7

APPENDICES

- APPENDIX A - MAPS
- APPENDIX B - CALCULATIONS
- APPENDIX C - PLANS
- APPENDIX D - GEOTECHNICAL REPORT

## I. PURPOSE OF REPORT

This report describes the proposed improvements compliance with the City of Keizer's Design Standards (February 2023)-Chapter 400.

## II. PROJECT DESCRIPTION

The site is located at 6255 McLeod Lane NE in Keizer. The property by McLeod Lane NE to the East, and private property to the north, south, and west.

### A. EXISTING CONDITION

The existing site is currently developed with what appears to be an abandoned single-family home.

The existing site is not located within a FEMA flood zone per FEMA flood map 41047C0194G, effective 1/19/2000.

### B. PROPOSED CONDITION

The proposed development includes a 6-lot subdivision and a lot for the private access street. This application is for the subdivision only and infrastructure improvements only. The proposed residential structures will be part of a future application, however, the stormwater design has been master planned for the entire residential site development.

The proposed site will need to alter the natural drainage pattern slightly to direct runoff towards the proposed stormwater planters. Ultimately the runoff will discharge to McLeod public storm drain main.

## GEOTECHNICAL FINDINGS

Based on the Geotechnical Report from GeoPacific Project No. 23-6474 on January 16, 2024, groundwater was not encountered at a depth of 10 however, depths of groundwater have been recorded from 15 to 30 feet. Infiltration rate were tested at depth of 4.5-ft at a rate of 0.0 in/hr and a depth of 9-ft at a rate of 0.48 in/hr.

For the purposes of this stormwater report, infiltration was not a viable solution, given the depth to a low permeability soil, as well as the provided groundwater table.

### III. METHODOLOGY

The City of Keizer's Design Standards (February 2023)-Chapter 400 were implemented for the design of the onsite stormwater system, as follows:

Projects greater than 5,000 square feet of new or replaced impervious surface are required to meet the full requirements for treatment, flow control, and retention of stormwater as provided below. This proposed project exceeds this new or replaced 5,000 square foot of impervious area.

#### **Stormwater Treatment**

The entire WQE will be required to retain and treat and shall conform to NPDES, TMDL and WPCF requirements and reduce the discharge of the listed pollutants to the Waters of the State. All treatment facilities will be designed to utilize the GSI to the MEF.

#### **Stormwater Retention**

The hierarchy to be followed in determining project specific applicable facility retention requirements based on the Design Infiltration Rates for the site or the Point of Connection as follows;

**1. Design Infiltration Rate greater than 2 inches per hour:**

The project facility shall retain and treat the entire WQE. The project facility shall retain all stormwater runoff up to and including the 100-year design storm event with no release allowed.

**2. Project is located in an Unserved Stormwater Area (regardless of design infiltration rate):**

The project facility shall retain and treat the entire WQE. The project facility shall retain all stormwater runoff from design storm events up to and including the 100-year design storm event with no release allowed.

**3. Design Infiltration Rate between 0.75 inches and 2 inches per hour:**

The facility shall retain and treat the entire WQE. In addition, the facility shall retain stormwater runoff for the 5-year, 10-year, 25-year design storm events with an allowable release rate up to the predeveloped 5-year design storm event. Runoff for the 50-year and 100-year design storm events shall be retained with an allowable release rate up to the predeveloped 25-year design storm event.

**4. Design Infiltration Rate less than 0.75 inches per hour:**

The facility shall retain and treat the entire WQE to the MEF. The facility shall also retain stormwater runoff for the 5-year, 10-year, 25-year, 50-year, and 100-year design storm events, not allowing any increase in runoff for all storm events listed.

**5. "Critical Basin" Point of Connection (regardless of design infiltration rate):**

The facility shall retain and treat the entire WQE to the MEF. The facility shall also retain stormwater runoff for the 2-year, 5-year, 10-year, 25-year, 50-year, and 100-year design storm events, not allowing any increase in runoff all storm events listed.

Based on the infiltration rate listed above, **Item 4** is applicable to our site.

## IV. CALCULATIONS

Two methods for sizing stormwater facilities may be used;

1. The Simplified Method, and
2. The Engineered Method.

Due to the overall site area constraints for the stormwater design, the Engineered Method was utilized for the sizing of the infiltration unit, as demonstrated below.

Method: Santa Barbara Urban Hydrograph (SBUH) Method

Program: HydroCAD 10.20-2g

Storm Event: Type 1-A 24-Hour Rainfall Distribution:

Water Quality Event: 1.38 inches  
 2-year Event: 2.20 inches  
 5-year Event: 2.70 inches  
 10-year Event: 3.20 inches  
 25-year Event: 3.60 inches  
 50-year Event: 4.10 inches  
 100-year Event: 4.40 inches

Tc: Minimum 5 Min

Soil Group: Group D

Curve Number:

Land Cover Category	Curve Numbers for Hydrologic Soil Group			
	A	B	C	D
<b>Impervious Surface</b>	<b>98</b>	<b>98</b>	<b>98</b>	<b>98</b>
<b>Pervious Land Cover</b>				
Pre-developed	35	58	72	79
Unamended Soils	72	82	87	89
Amended Soils	39	61	74	80

## V. SUMMARY

Planter strip swales are proposed at the east side of the property. The proposed site will be raised slightly to direct runoff towards the proposed planter strip swales, that treat and store the required runoff while slowly releasing into the existing city storm drain main in McLeod.

Below is a summary of the calculations.

CATCHMENT AND FACILITY TABLE						
CATCHMENT/ FACILITY ID	TOTAL AREA (SF)/(AC.)	IMPERVIOUS AREA (SF)	PERVIOUS AREA (SF)	OWNERSHIP (PRIVATE/ PUBLIC)	FACILITY TYPE	FACILITY SIZE
A	41,839	28,416	13,423	PRIVATE	Planter Strip Swale	1,500

\*Impervious Improvements + (60% Impervious of Each Lot)

PRE VS. POST CONSTRUCTION FLOW RATES												
FACILITY ID	PEAK FLOW RATE (CFS)											
	2-YEAR STORM		5 YEAR STORM		10 YEAR STORM		25 YEAR STORM		50 YEAR STORM		100 YEAR STORM	
PROJECT SITE	PRE	POST	PRE	POST	PRE	POST	PRE	POST	PRE	POST	PRE	POST
A	0.08	0.08	0.14	0.12	0.21	0.2	0.28	0.25	0.36	0.3	0.41	0.32


WATER QUALITY TREATMENT REQUIREMENTS				
CATCHMENT/ FACILITY ID	WQV (IN)	WQV (CF)	80% OF WQV	RAIN GARDEN ALLOWABLE VOLUME
A	1.38	3,006	2,405	3,277

APPENDIX A – MAPS




APPENDIX B – CALCULATIONS



# POST DEVELOPMENT



A-1



PA



## Post-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 2

### Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Yr	Type IA 24-hr		Default	24.00	1	2.20	2
2	5-YR	Type IA 24-hr		Default	24.00	1	2.70	2
3	10-Yr	Type IA 24-hr		Default	24.00	1	3.20	2
4	25-YR	Type IA 24-hr		Default	24.00	1	3.60	2
5	50-YR	Type IA 24-hr		Default	24.00	1	4.10	2
6	100-Yr	Type IA 24-hr		Default	24.00	1	4.40	2
7	WQV	Type IA 24-hr		Default	24.00	1	1.38	2

## Post-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 3

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.652	98	(1S)
0.308	80	(1S)
<b>0.960</b>	<b>92</b>	<b>TOTAL AREA</b>

## Post-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 4

### Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.960	Other	1S
<b>0.960</b>		<b>TOTAL AREA</b>

## Post-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 5

### Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	0.960	0.960		1S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.960</b>	<b>0.960</b>	<b>TOTAL AREA</b>	

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 2-Yr Rainfall=2.20"

Printed 1/23/2024

Page 6

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=1.56"

Tc=5.0 min CN=80/98 Runoff=0.36 cfs 0.125 af

**Pond 14P: PA**

Peak Elev=102.82' Storage=1,771 cf Inflow=0.36 cfs 0.125 af

Primary=0.08 cfs 0.125 af Secondary=0.00 cfs 0.000 af Outflow=0.08 cfs 0.125 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.125 af Average Runoff Depth = 1.56"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 2-Yr Rainfall=2.20"

Printed 1/23/2024

Page 7

**Summary for Subcatchment 1S: A-1**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.36 cfs @ 7.92 hrs, Volume= 0.125 af, Depth= 1.56"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 2-Yr Rainfall=2.20"

	Area (sf)	CN	Description
	28,416	98	
*	13,423	80	
	41,839	92	Weighted Average
	13,423	80	32.08% Pervious Area
	28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph





**Post-Development**

Type IA 24-hr 2-Yr Rainfall=2.20"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 8

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 1.56" for 2-Yr event  
 Inflow = 0.36 cfs @ 7.92 hrs, Volume= 0.125 af  
 Outflow = 0.08 cfs @ 10.27 hrs, Volume= 0.125 af, Atten= 77%, Lag= 140.8 min  
 Primary = 0.08 cfs @ 10.27 hrs, Volume= 0.125 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 102.82' @ 10.27 hrs Surf.Area= 1,500 sf Storage= 1,771 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 404.2 min calculated for 0.125 af (100% of inflow)  
 Center-of-Mass det. time= 404.9 min ( 1,110.1 - 705.2 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.08 cfs @ 10.27 hrs HW=102.82' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 8.47 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.02 cfs @ 4.24 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.01 cfs @ 2.53 fps)
- ↑5=Orifice/Grate ( Controls 0.00 cfs)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 2-Yr Rainfall=2.20"

Printed 1/23/2024

Page 9

**Pond 14P: PA**

Hydrograph



**Post-Development**

Type IA 24-hr 5-YR Rainfall=2.70"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 10

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=2.01"

Tc=5.0 min CN=80/98 Runoff=0.47 cfs 0.161 af

**Pond 14P: PA**

Peak Elev=103.12' Storage=2,212 cf Inflow=0.47 cfs 0.161 af

Primary=0.12 cfs 0.161 af Secondary=0.00 cfs 0.000 af Outflow=0.12 cfs 0.161 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.161 af Average Runoff Depth = 2.01"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 5-YR Rainfall=2.70"

Printed 1/23/2024

Page 11

**Summary for Subcatchment 1S: A-1**

[49] Hint:  $T_c < 2dt$  may require smaller dt

Runoff = 0.47 cfs @ 7.92 hrs, Volume= 0.161 af, Depth= 2.01"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 5-YR Rainfall=2.70"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph



**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 5-YR Rainfall=2.70"

Printed 1/23/2024

Page 12

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 2.01" for 5-YR event  
 Inflow = 0.47 cfs @ 7.92 hrs, Volume= 0.161 af  
 Outflow = 0.12 cfs @ 9.46 hrs, Volume= 0.161 af, Atten= 74%, Lag= 92.1 min  
 Primary = 0.12 cfs @ 9.46 hrs, Volume= 0.161 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 103.12' @ 9.46 hrs Surf.Area= 1,500 sf Storage= 2,212 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 373.5 min calculated for 0.161 af (100% of inflow)  
 Center-of-Mass det. time= 372.9 min ( 1,072.4 - 699.4 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.12 cfs @ 9.46 hrs HW=103.12' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 8.88 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.03 cfs @ 5.00 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.02 cfs @ 3.66 fps)
- ↑5=Orifice/Grate (Orifice Controls 0.03 cfs @ 1.18 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 5-YR Rainfall=2.70"

Printed 1/23/2024

Page 13

**Pond 14P: PA**

Hydrograph



**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 14

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=2.47"

Tc=5.0 min CN=80/98 Runoff=0.58 cfs 0.197 af

**Pond 14P: PA**

Peak Elev=103.31' Storage=2,490 cf Inflow=0.58 cfs 0.197 af

Primary=0.20 cfs 0.197 af Secondary=0.00 cfs 0.000 af Outflow=0.20 cfs 0.197 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.197 af Average Runoff Depth = 2.47"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 15

**Summary for Subcatchment 1S: A-1**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.58 cfs @ 7.92 hrs, Volume= 0.197 af, Depth= 2.47"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 10-Yr Rainfall=3.20"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph





**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 16

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 2.47" for 10-Yr event  
 Inflow = 0.58 cfs @ 7.92 hrs, Volume= 0.197 af  
 Outflow = 0.20 cfs @ 8.89 hrs, Volume= 0.197 af, Atten= 65%, Lag= 58.3 min  
 Primary = 0.20 cfs @ 8.89 hrs, Volume= 0.197 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 103.31' @ 8.89 hrs Surf.Area= 1,500 sf Storage= 2,490 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 335.8 min calculated for 0.197 af (100% of inflow)  
 Center-of-Mass det. time= 336.5 min ( 1,031.3 - 694.8 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.20 cfs @ 8.89 hrs HW=103.31' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 9.11 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.03 cfs @ 5.41 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.02 cfs @ 4.21 fps)
- ↑5=Orifice/Grate (Orifice Controls 0.10 cfs @ 2.04 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 17

**Pond 14P: PA**

Hydrograph



**Post-Development**

Type IA 24-hr 25-YR Rainfall=3.60"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 18

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=2.84"

Tc=5.0 min CN=80/98 Runoff=0.67 cfs 0.227 af

**Pond 14P: PA**

Peak Elev=103.49' Storage=2,766 cf Inflow=0.67 cfs 0.227 af

Primary=0.25 cfs 0.227 af Secondary=0.00 cfs 0.000 af Outflow=0.25 cfs 0.227 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.227 af Average Runoff Depth = 2.84"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 25-YR Rainfall=3.60"

Printed 1/23/2024

Page 19

**Summary for Subcatchment 1S: A-1**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.67 cfs @ 7.92 hrs, Volume= 0.227 af, Depth= 2.84"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 25-YR Rainfall=3.60"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph



**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 25-YR Rainfall=3.60"

Printed 1/23/2024

Page 20

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 2.84" for 25-YR event  
 Inflow = 0.67 cfs @ 7.92 hrs, Volume= 0.227 af  
 Outflow = 0.25 cfs @ 8.75 hrs, Volume= 0.227 af, Atten= 63%, Lag= 50.3 min  
 Primary = 0.25 cfs @ 8.75 hrs, Volume= 0.227 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 103.49' @ 8.75 hrs Surf.Area= 1,500 sf Storage= 2,766 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 313.9 min calculated for 0.227 af (100% of inflow)  
 Center-of-Mass det. time= 314.6 min ( 1,006.3 - 691.6 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.25 cfs @ 8.75 hrs HW=103.49' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 9.35 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.03 cfs @ 5.79 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.03 cfs @ 4.69 fps)
- ↑5=Orifice/Grate (Orifice Controls 0.14 cfs @ 2.90 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 25-YR Rainfall=3.60"

Printed 1/23/2024

Page 21

**Pond 14P: PA**

Hydrograph



**Post-Development**

Type IA 24-hr 50-YR Rainfall=4.10"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 22

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=3.31"

Tc=5.0 min CN=80/98 Runoff=0.78 cfs 0.265 af

**Pond 14P: PA**

Peak Elev=103.74' Storage=3,141 cf Inflow=0.78 cfs 0.265 af

Primary=0.30 cfs 0.265 af Secondary=0.00 cfs 0.000 af Outflow=0.30 cfs 0.265 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.265 af Average Runoff Depth = 3.31"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 50-YR Rainfall=4.10"

Printed 1/23/2024

Page 23

**Summary for Subcatchment 1S: A-1**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.78 cfs @ 7.92 hrs, Volume= 0.265 af, Depth= 3.31"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 50-YR Rainfall=4.10"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph





**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 50-YR Rainfall=4.10"

Printed 1/23/2024

Page 24

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 3.31" for 50-YR event  
 Inflow = 0.78 cfs @ 7.92 hrs, Volume= 0.265 af  
 Outflow = 0.30 cfs @ 8.69 hrs, Volume= 0.265 af, Atten= 61%, Lag= 46.3 min  
 Primary = 0.30 cfs @ 8.69 hrs, Volume= 0.265 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 103.74' @ 8.69 hrs Surf.Area= 1,500 sf Storage= 3,141 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 292.1 min calculated for 0.265 af (100% of inflow)  
 Center-of-Mass det. time= 291.5 min ( 979.7 - 688.2 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.30 cfs @ 8.69 hrs HW=103.74' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 9.65 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.03 cfs @ 6.27 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.03 cfs @ 5.27 fps)
- ↑5=Orifice/Grate (Orifice Controls 0.19 cfs @ 3.77 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 50-YR Rainfall=4.10"

Printed 1/23/2024

Page 25

**Pond 14P: PA**

Hydrograph



**Post-Development**

Type IA 24-hr 100-Yr Rainfall=4.40"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 26

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=3.59"

Tc=5.0 min CN=80/98 Runoff=0.85 cfs 0.287 af

**Pond 14P: PA**

Peak Elev=103.84' Storage=3,277 cf Inflow=0.85 cfs 0.287 af

Primary=0.32 cfs 0.285 af Secondary=0.01 cfs 0.000 af Outflow=0.32 cfs 0.285 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.287 af Average Runoff Depth = 3.59"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 100-Yr Rainfall=4.40"

Printed 1/23/2024

Page 27

**Summary for Subcatchment 1S: A-1**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.85 cfs @ 7.91 hrs, Volume= 0.287 af, Depth= 3.59"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 100-Yr Rainfall=4.40"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph



**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 100-Yr Rainfall=4.40"

Printed 1/23/2024

Page 28

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

[93] Warning: Storage range exceeded by 0.01'

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 3.59" for 100-Yr event  
 Inflow = 0.85 cfs @ 7.91 hrs, Volume= 0.287 af  
 Outflow = 0.32 cfs @ 8.61 hrs, Volume= 0.285 af, Atten= 62%, Lag= 41.9 min  
 Primary = 0.32 cfs @ 8.61 hrs, Volume= 0.285 af  
 Secondary = 0.01 cfs @ 8.61 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 103.84' @ 8.61 hrs Surf.Area= 1,500 sf Storage= 3,277 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 288.4 min calculated for 0.285 af (99% of inflow)  
 Center-of-Mass det. time= 282.4 min ( 968.8 - 686.4 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.32 cfs @ 8.61 hrs HW=103.84' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.05 cfs @ 9.77 fps)
- ↑3=Orifice/Grate (Orifice Controls 0.04 cfs @ 6.45 fps)
- ↑4=Orifice/Grate (Orifice Controls 0.03 cfs @ 5.48 fps)
- ↑5=Orifice/Grate (Orifice Controls 0.20 cfs @ 4.06 fps)

**Secondary OutFlow** Max=0.00 cfs @ 8.61 hrs HW=103.84' (Free Discharge)

- ↑2=Orifice/Grate (Weir Controls 0.00 cfs @ 0.25 fps)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr 100-Yr Rainfall=4.40"

Printed 1/23/2024

Page 29

**Pond 14P: PA**

Hydrograph



**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024

Page 30

Time span=0.10-96.00 hrs, dt=0.05 hrs, 1919 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: A-1**

Runoff Area=41,839 sf 67.92% Impervious Runoff Depth=0.86"

Tc=5.0 min CN=80/98 Runoff=0.20 cfs 0.069 af

**Pond 14P: PA**

Peak Elev=101.44' Storage=1,047 cf Inflow=0.20 cfs 0.069 af

Primary=0.03 cfs 0.069 af Secondary=0.00 cfs 0.000 af Outflow=0.03 cfs 0.069 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.069 af Average Runoff Depth = 0.86"**  
**32.08% Pervious = 0.308 ac 67.92% Impervious = 0.652 ac**

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024

Page 31

**Summary for Subcatchment 1S: A-1**

[49] Hint:  $T_c < 2dt$  may require smaller dt

Runoff = 0.20 cfs @ 7.93 hrs, Volume= 0.069 af, Depth= 0.86"  
 Routed to Pond 14P : PA


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-96.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr WQV Rainfall=1.38"

Area (sf)	CN	Description
28,416	98	
* 13,423	80	
41,839	92	Weighted Average
13,423	80	32.08% Pervious Area
28,416	98	67.92% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: A-1**

Hydrograph





**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024

Page 32

**Summary for Pond 14P: PA**

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.960 ac, 67.92% Impervious, Inflow Depth = 0.86" for WQV event  
 Inflow = 0.20 cfs @ 7.93 hrs, Volume= 0.069 af  
 Outflow = 0.03 cfs @ 13.82 hrs, Volume= 0.069 af, Atten= 83%, Lag= 353.2 min  
 Primary = 0.03 cfs @ 13.82 hrs, Volume= 0.069 af  
 Secondary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-96.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 101.44' @ 13.82 hrs Surf.Area= 1,500 sf Storage= 1,047 cf  
 Flood Elev= 104.00' Surf.Area= 1,500 sf Storage= 3,277 cf

Plug-Flow detention time= 424.3 min calculated for 0.069 af (100% of inflow)  
 Center-of-Mass det. time= 425.0 min ( 1,144.0 - 719.0 )

Volume	Invert	Avail.Storage	Storage Description			
#1	99.68'	3,277 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.68	1,500	300.0	0.0	0	0	1,500
101.00	1,500	300.0	40.0	792	792	1,896
101.33	1,500	300.0	40.0	198	990	1,995
102.83	1,500	300.0	35.0	788	1,777	2,445
103.83	1,500	300.0	100.0	1,500	3,277	2,745

Device	Routing	Invert	Outlet Devices		
#1	Primary	99.68'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#2	Secondary	103.83'	<b>6.0" Horiz. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#3	Primary	102.00'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#4	Primary	102.50'	<b>1.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads
#5	Primary	103.00'	<b>3.0" Vert. Orifice/Grate</b>	C= 0.600	Limited to weir flow at low heads

**Primary OutFlow** Max=0.03 cfs @ 13.82 hrs HW=101.44' (Free Discharge)

- ↑1=Orifice/Grate (Orifice Controls 0.03 cfs @ 6.31 fps)
- 3=Orifice/Grate ( Controls 0.00 cfs)
- 4=Orifice/Grate ( Controls 0.00 cfs)
- 5=Orifice/Grate ( Controls 0.00 cfs)

**Secondary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=99.68' (Free Discharge)

- ↑2=Orifice/Grate ( Controls 0.00 cfs)

**Post-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC


Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024


Page 33

**Pond 14P: PA**



Hydrograph



# PRE DEVELOPMENT



EX-1



## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 2

### Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Yr	Type IA 24-hr		Default	24.00	1	2.20	2
2	5-YR	Type IA 24-hr		Default	24.00	1	2.70	2
3	10-Yr	Type IA 24-hr		Default	24.00	1	3.20	2
4	25-YR	Type IA 24-hr		Default	24.00	1	3.60	2
5	50-YR	Type IA 24-hr		Default	24.00	1	4.10	2
6	100-Yr	Type IA 24-hr		Default	24.00	1	4.40	2
7	WQV	Type IA 24-hr		Default	24.00	1	1.38	2

## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 3

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.960	79	(1S)
<b>0.960</b>	<b>79</b>	<b>TOTAL AREA</b>

## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 4

### Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.960	Other	1S
<b>0.960</b>		<b>TOTAL AREA</b>

## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Printed 1/23/2024

Page 5

### Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	0.960	0.960		1S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.960</b>	<b>0.960</b>	<b>TOTAL AREA</b>	

## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 2-Yr Rainfall=2.20"

Printed 1/23/2024

Page 6

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

### Subcatchment1S: EX-1

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=0.64"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.08 cfs 0.051 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.051 af Average Runoff Depth = 0.64"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**



**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 2-Yr Rainfall=2.20"

Printed 1/23/2024

Page 7

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.08 cfs @ 8.10 hrs, Volume= 0.051 af, Depth= 0.64"  
Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
Type IA 24-hr 2-Yr Rainfall=2.20"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 5-YR Rainfall=2.70"

Printed 1/23/2024

Page 8

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

### Subcatchment 1S: EX-1

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=0.97"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.14 cfs 0.078 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.078 af Average Runoff Depth = 0.97"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**

**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 5-YR Rainfall=2.70"

Printed 1/23/2024

Page 9

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.14 cfs @ 8.06 hrs, Volume= 0.078 af, Depth= 0.97"  
Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
Type IA 24-hr 5-YR Rainfall=2.70"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 10

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: EX-1**

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=1.34"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.21 cfs 0.107 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.107 af Average Runoff Depth = 1.34"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**

**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 10-Yr Rainfall=3.20"

Printed 1/23/2024

Page 11

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.21 cfs @ 8.05 hrs, Volume= 0.107 af, Depth= 1.34"  
 Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 10-Yr Rainfall=3.20"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 25-YR Rainfall=3.60"

Printed 1/23/2024

Page 12

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

### Subcatchment 1S: EX-1

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=1.64"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.28 cfs 0.132 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.132 af Average Runoff Depth = 1.64"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**

**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 25-YR Rainfall=3.60"

Printed 1/23/2024

Page 13

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.28 cfs @ 8.05 hrs, Volume= 0.132 af, Depth= 1.64"  
Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
Type IA 24-hr 25-YR Rainfall=3.60"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



**Pre-Development**

Type IA 24-hr 50-YR Rainfall=4.10"

Prepared by 7 Oaks Engineering, Inc

Printed 1/23/2024

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Page 14

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: EX-1**

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=2.04"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.36 cfs 0.164 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.164 af Average Runoff Depth = 2.04"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**



**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 50-YR Rainfall=4.10"

Printed 1/23/2024

Page 15

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.36 cfs @ 8.04 hrs, Volume= 0.164 af, Depth= 2.04"  
Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
Type IA 24-hr 50-YR Rainfall=4.10"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 100-Yr Rainfall=4.40"

Printed 1/23/2024

Page 16

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

### Subcatchment 1S: EX-1

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=2.29"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.41 cfs 0.184 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.184 af Average Runoff Depth = 2.29"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**

**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr 100-Yr Rainfall=4.40"

Printed 1/23/2024

Page 17

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.41 cfs @ 8.04 hrs, Volume= 0.184 af, Depth= 2.29"  
 Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 100-Yr Rainfall=4.40"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



## Pre-Development

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024

Page 18

Time span=0.10-48.00 hrs, dt=0.05 hrs, 959 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

### Subcatchment1S: EX-1

Runoff Area=41,839 sf 0.00% Impervious Runoff Depth=0.21"

Flow Length=120' Slope=0.0070 '/' Tc=20.8 min CN=79/0 Runoff=0.01 cfs 0.016 af

**Total Runoff Area = 0.960 ac Runoff Volume = 0.016 af Average Runoff Depth = 0.21"**

**100.00% Pervious = 0.960 ac 0.00% Impervious = 0.000 ac**

**Pre-Development**

Prepared by 7 Oaks Engineering, Inc

HydroCAD® 10.20-4a s/n 12691 © 2023 HydroCAD Software Solutions LLC

Type IA 24-hr WQV Rainfall=1.38"

Printed 1/23/2024

Page 19

**Summary for Subcatchment 1S: EX-1**

Runoff = 0.01 cfs @ 17.00 hrs, Volume= 0.016 af, Depth= 0.21"  
 Routed to nonexistent node 14P


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.10-48.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr WQV Rainfall=1.38"

Area (sf)	CN	Description
* 41,839	79	
41,839	79	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	120	0.0070	0.10		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 2.20"

**Subcatchment 1S: EX-1**

Hydrograph



APPENDIX C – PLANS

**GENERAL NOTES:**

1. ALL CONSTRUCTION, MATERIALS, AND WORKMANSHIP SHALL CONFORM TO THE LATEST STANDARDS AND PRACTICES OF THE CITY OF KEIZER, THE OREGON STRUCTURAL SPECIALTY CODE (BUILDING CODE), OREGON PLUMBING SPECIALTY (PLUMBING CODE), AND THE OREGON FIRE CODE (FIRE CODE), LATEST EDITIONS.
2. ALL PERMIT AND LICENSES NECESSARY FOR THE EXECUTION AND COMPLETION OF THE WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION.
3. ALL EXCAVATORS MUST COMPLY WITH THE RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER, INCLUDING NOTIFICATION OF ALL OWNERS OF UNDERGROUND UTILITIES AT LEAST 48 BUSINESS HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090 AND ORS 757.541 TO 757.57. THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503.232.1987 AND THE LOCAL "CALL 48 HOURS BEFORE YOU DIG NUMBER" IS 503.246.6699.
4. THE LOCATION OF EXISTING UNDERGROUND UTILITIES SHOWN ON THE PLAN IS FOR INFORMATION ONLY AND IS NOT GUARANTEED TO BE ACCURATE. CONTRACTOR SHALL VERIFY ELEVATIONS OF ALL UNDERGROUND UTILITY CONNECTION POINTS PRIOR TO COMMENCING WITH CONSTRUCTION AND SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF 7 OAKS ENGINEERING, INC. POTHOLE ALL CROSSINGS AS NECESSARY BEFORE CONSTRUCTION TO PREVENT GRADE AND ALIGNMENT CONFLICTS.
5. 7 OAKS ENGINEERING, INC. ASSUMES NO RESPONSIBILITY FOR ANY DISCREPANCIES ENCOUNTERED BETWEEN THE CURRENT FIELD CONDITIONS AND THE INFORMATION SHOWN ON THE SURVEY MAP (PERFORMED BY FORTY FIVE NORTH SURVEYING, LLC). THE CONTRACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES TO THE OWNER'S REPRESENTATIVE.

**GRADING AND PAVING NOTES:**

1. ALL SURFACES SHALL HAVE A MINIMUM 1.0% SLOPE UNLESS OTHERWISE NOTED ON THE PLANS. ALL SURFACES SHALL MEET EXISTING GRADES SMOOTHLY AND EVENLY AND MAINTAIN CONSTANT SLOPES UNLESS OTHERWISE NOTED ON THE PLANS.
2. THE CONTRACTOR SHALL NOTIFY 7 OAKS ENGINEERING, INC. IF THE GRADING PLAN DOES NOT PROVIDE POSITIVE DRAINAGE OR IF SLOPE CALLOUTS DO NOT MATCH SPOT GRADES.
3. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EXISTING SITE AND DRAINAGE PATTERNS AND THE PROTECTION OF EXISTING ENGINEERED DRAINAGE FACILITIES.
4. THE CONTRACTOR SHALL REPLACE AND RESTORE AREAS NOT SCHEDULED FOR CONSTRUCTION TO THEIR ORIGINAL CONDITION AND TO THE APPROVAL OF THE OWNERS REPRESENTATIVE.
5. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION WHEN WORKING IN AREAS ADJACENT TO EXISTING TREES IN ORDER TO MINIMIZE DISTURBANCES TO THE ROOTS. THE CONTRACTOR SHALL INSTALL TREE PROTECTION FENCING PER CITY OF SALEM TREE CODE. NO PARKING VEHICLES UNDER TREES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND DISPOSAL OF EXISTING AC, CURBS, SIDEWALKS, AND OTHER SITE ELEMENTS WITHIN THE LIMITS OF DEMOLITION., UNLESS OTHERWISE NOTED ON PLANS. DISPOSE OF DEMOLISHED ITEMS OFF-SITE IN A LEGAL MANNER.
7. ACTUAL LINES AND GRADES OF EXCAVATION SHALL BE STAKED BY A QUALIFIED SURVEYOR. BASED ON THE INFORMATION SHOWN ON THE PLANS, THE CONTRACTOR SHALL RETAIN A SURVEYOR LICENSED IN OREGON.
8. ADJUST ALL INCIDENTAL STRUCTURES, MANHOLE LIDS, VALVE BOXES, ETC. TO FINISH GRADE.
9. PAVING WILL NOT BE ALLOWED DURING WET OR COLD WEATHER.
10. ALL CONSTRUCTION WITHIN THE CITY RIGHT-OF-WAY SHALL HAVE AN APPROVED TRAFFIC CONTROL PLAN.
11. ALL CONSTRUCTION WITHIN THE CITY RIGHT-OF-WAY SHALL BE PERMITTED UNDER SEPARATE PERMIT.
12. PRIOR TO THE PLACEMENT OF AGGREGATE BASE MATERIALS RELATED TO SITE PAVING, A GEOTECHNICAL ENGINEER SHOULD BE PRESENT TO OBSERVE AND EVALUATE THE SUBGRADE SOIL CONDITIONS, AS OUTLINED IN THE GEOTECHNICAL REPORT.

**UTILITY NOTES:**

1. MATERIALS SHALL BE NEW. THE USE OF MANUFACTURER'S NAMES, MODELS, AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, AND USEFULNESS. PROPOSED SUBSTITUTIONS WILL REQUIRE WRITTEN APPROVAL FROM CITY ENGINEER PRIOR TO INSTALLATION.
2. ALL TRENCH BACKFILL SHALL BE SHOWN ON THE PIPE BEDDING AND BACKFILL DETAIL. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER IS NOT PERMITTED.
3. CONNECTIONS TO EXISTING UTILITIES SHALL CONFORM WITH THE CITY'S ENGINEERING DESIGN MANUAL AND STANDARD PLANS.
4. ALL WATER AND FIRE PROTECTION PIPE SHALL HAVE A MINIMUM 36-INCH COVER TO FINISHED GRADE.
5. ALL WATER LINES SHALL BE THOROUGHLY FLUSHED, CHLORINATED AND TESTED IN ACCORDANCE WITH OREGON STATE HEALTH DEPARTMENT PRIOR TO ANY METER HOOK-UP SERVICE.
6. BEGIN LAYING STORM AND SANITARY SEWER PIPE AT THE LOW POINT OF THE SYSTEM TRUE TO GRADE AND ALIGNMENT INDICATED WITH UNBROKEN CONTINUITY OF INVERT. ESTABLISH LINE AND GRADE FOR THE STORM AND SANITARY SEWER PIPE BY USE OF A LASER.
7. CONTRACTOR SHALL MAINTAIN A MINIMUM 5' HORIZONTAL AND 18" VERTICAL SEPARATION BETWEEN ALL EXISTING AND PROPOSED WATER AND SANITARY SEWER LINES.
8. FOR CROSSINGS OF WATER LINES AND SANITARY SEWER LINES, THE OREGON STATE HEALTH DEPARTMENT CRITERIA SHALL APPLY.
9. EXISTING STORM OR SANITARY LATERALS TO BE UTILIZED FOR NEW SYSTEM MUST BE VIDEO INSPECTED WITH CITY INSPECTOR PRESENT PRIOR TO CONNECTION.
10. ALL NEW DRYWELLS MUST BE ACCESSIBLE PER OREGON DEPARTMENT OF ENVIRONMENTAL SERVICES QUALITY REQUIREMENTS.
11. THE CONTRACTOR SHALL VACUUM OUT ALL TRAPPED INLETS, MANHOLES, AND DRYWELLS AT THE END OF CONSTRUCTION.
12. CONTRACTOR SHALL EXERCISE CARE IN ALL OPERATIONS TO PROTECT EXISTING UNDERGROUND UTILITIES, ANY DAMAGE RESULTING FROM THIS WORK MUST BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THE APPROVAL OF THE OWNER'S REPRESENTATIVE.

**BASIS OF BEARINGS:**

BASIS OF BEARINGS AND COORDINATE SYSTEM IS BASED ON OREGON STATE PLANE NORTH ZONE, NAD83(2011), EPOCH 2010.00. ALL DISTANCE SHOWN HEREON ARE GROUND DISTANCE.

**BENCH MARK:**

ELEVATIONS WERE ESTABLISHED BY GPS RTK OBSERVATIONS TO CITY OF SALEM BENCHMARK "KSUN". MARK IS AN ALUMINUM DISK IN A CONCRETE UTILITY PAD ON THE NORTH SIDE OF SUNSET AVENUE N, APPROXIMATELY 100 FEET WEST OF RIVER ROAD N. ELEVATION = 134.38' (CITY OF SALEM DATUM, NGVD 29).

**NOTICE TO EXCAVATORS:**

ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.  
(NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS


**Dig Safely.**

Call the Oregon One-Call Center  
DIAL 811 or 1-800-332-2344

# PRELIMINARY SUDIVISION

## PLANS

AT 6255 MCLEOD  
KEIZER, OR.



**INDEX MAP**

SCALE: 1" = 30'

**ABBREVIATIONS:**

PL	PROPERTY LINE	TYP.	TYPICAL
FF	FINISHED FLOOR	MIN.	MINIMUM
TC	TOP OF CURB	SS	SANITARY SEWER
FS	FINISHED SURFACE	SD	STORM DRAIN
FL	FLOW LINE	CF	CURB FACE
FG	FINISHED GRADE	WM	WATER METER
GB	GRADE BREAK	FDC	FIRE DEPARTMENT CONNECTION
CL	CENTERLINE	APN	ACCESSOR'S PARCEL MAP
R	RIDGE LINE	SQ.FT	SQUARE FEET
R/W	RIGHT OF WAY	INV.	INVERT
WV	WATER VALVE	BF	BACKFLOW
PR.	PROPOSED	CFS	CUBIC FEET PER SECOND
NAP	NOT A PART	SCH.	SCHEDULE
FT	FEET	PVC	POLYVINYL CHLORIDE
EV	ELECTRIC VEHICLE	SDR	SPECIAL DRAWING RIGHT
CAV	CLEAN AIR VEHICLE	PSI	POUNDS PER SQUARE INCH
STD.	STANDARD	NFPA	NATIONAL FIRE PREVENTION ASSOCIATION
AC.	ACRES	CB	CATCH BASIN
CUP	CONDITIONAL USE PERMIT	D	DIAMETER
EX.	EXISTING	VCP	VITRIFIED CLAY PIPE

**SHEET INDEX:**


- 1 - TITLE SHEET
- 2 - PRELIMINARY GRADING PLAN
- 3 - PRELIMINARY UTILITY PLAN
- 4 - PRELIMINARY SUBDIVISION PLAN
- 5 - TREE PRESERVATION PLAN

**ENGINEER'S NOTICE TO CONTRACTOR:**

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITIES OR STRUCTURES SHOWN IN THESE PLANS ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS, AND TO THE BEST OF OUR KNOWLEDGE, THERE ARE NOT EXISTING UTILITIES EXCEPT THOSE SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE ALL PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN, AND ANY OTHER LINES OR STRUCTURES NOT SHOWN ON THESE PLANS, AND IS RESPONSIBLE FOR THE PROTECTION OF ANY DAMAGE TO THESE LINES OR STRUCTURES.

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENTS SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS EMPLOYEES, AND AGENTS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE TO REPORT DISCREPANCIES IN PLANS AND/OR FIELD CONDITIONS IMMEDIATELY TO THE DESIGN ENGINEER FOR RESOLUTION PRIOR TO CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DISCREPANCIES NOT SO REPORTED AND RESOLVED.




**VICINITY MAP**

NTS

**7 OAKS ENGINEERING**

345 WESTFIELD ST. #107  
SILVERTON, OR. 97381  
ADMIN@7OAKSENGINEERING.COM

STAMP:



NO	DATE	ISSUE DESCRIPTION

**PROJECT DIRECTORY:**

**ARCHITECT:**  
GEOFFREY JAMES ARCHITECT  
GJAMESARCHITECT@GMAIL.COM  
503.931.4120

**CIVIL ENGINEER:**  
7 OAKS ENGINEERING, INC.  
KIM JOHNSON, P.E.  
345 WESTFIELD ST. #107  
SILVERTON, OR. 97381  
503.308.8554  
KIM@7OAKSENGINEERING.COM

**SURVEY:**

FORTY FIVE NORTH SURVEYING, LLC  
7320 3RD STREET SE #145  
TURNER, OR. 97392  
503.588.3330

**UTILITY PURVEYORS:**

**WATER:**

CITY OF KEIZER  
930 CHEWAWA RD.  
KEIZER, OR. 97303

**STORM DRAIN:**

CITY OF KEIZER-PUBLIC WORKS  
930 CHEWAWA RD.  
KEIZER, OR. 97303

**SEWER:**

CITY OF SALEM  
555 LIBERTY STREET SE  
SALEM, OREGON.  
503.588.6311

**FIRE:**

CITY OF KEIZER  
930 CHEWAWA RD.  
KEIZER, OR. 97303

**ELECTRIC:**

PORTLAND GENERAL ELECTRIC  
KEN SPENCER  
KENNETH.SPENCER@PGN.COM  
503.970.7200

**NATURAL GAS:**

NORTHWEST NATURAL GAS COMPANY  
3123 BROADWAY ST NE  
SALEM, OR. 97303  
503.585.6611

**ROADWAYS:**

CITY OF KEIZER-PUBLIC WORKS  
930 CHEWAWA RD.  
KEIZER, OR. 97303

PROJECT NAME:  
**MCLEOD SUBDIVISION**

PROJECT ADDRESS:  
**6255 MCLEOD**


**KEIZER, OR.**

SHEET TITLE:

**TITLE SHEET**

DATE:  
**02/20/2024**

SHEET NUMBER:  
**1**



# 7 OAKS

**ENGINEERING**

345 WESTFIELD ST. #107  
SUNNYVALE, OR. 97381  
503.548.1965  
ADMIN@7OAKSENGINEERING.COM

STAMP:

NO	DATE	ISSUE DESCRIPTION

NO CHANGES, MODIFICATIONS OR REPRODUCTIONS TO BE MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.  
DIMENSIONS AND NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.  
THESE DRAWINGS MAY HAVE BEEN REPRODUCED AT A SIZE DIFFERENTLY THAN ORIGINALLY DRAWN. OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR USE OF INCORRECT SCALE.  
CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO PROCEEDING WITH CONSTRUCTION AND NOTIFY ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES OR CONFLICTS.

CC BY:      DRAWN BY:

PROJECT NAME:  
**MCLEOD SUBDIVISION**

PROJECT ADDRESS:  
**6255 MCLEOD**

**KEIZER, OR.**

SHEET TITLE:  
**PRELIMINARY GRADING PLAN**

DATE: 02/20/2024

SHEET NUMBER:  
**2**

**NOTICE TO EXCAVATORS:**

ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.

(NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS

**Dig Safely.**


Call the Oregon One-Call Center  
DIAL 811 or 1-800-332-2344

**ENGINEER'S NOTICE TO CONTRACTOR:**

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITIES OR STRUCTURES SHOWN IN THESE PLANS ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS, AND TO THE BEST OF OUR KNOWLEDGE, THERE ARE NOT EXISTING UTILITIES EXCEPT THOSE SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE ALL PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN, AND ANY OTHER LINES OR STRUCTURES NOT SHOWN ON THESE PLANS, AND IS RESPONSIBLE FOR THE PROTECTION OF ANY DAMAGE TO THESE LINES OR STRUCTURES.


CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENTS SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS EMPLOYEES, AND AGENTS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE TO REPORT DISCREPANCIES IN PLANS AND/OR FIELD CONDITIONS IMMEDIATELY TO THE DESIGN ENGINEER FOR RESOLUTION PRIOR TO CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DISCREPANCIES NOT SO REPORTED AND RESOLVED.









**NOTICE TO EXCAVATORS:**  
 ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.  
 (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS  
**Dig Safely.**  
 Call the Oregon One-Call Center  
 DIAL 811 or 1-800-332-2344


**ENGINEER'S NOTICE TO CONTRACTOR:**

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITIES OR STRUCTURES SHOWN IN THESE PLANS ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS, AND TO THE BEST OF OUR KNOWLEDGE, THERE ARE NOT EXISTING UTILITIES EXCEPT THOSE SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE ALL PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN, AND ANY OTHER LINES OR STRUCTURES NOT SHOWN ON THESE PLANS, AND IS RESPONSIBLE FOR THE PROTECTION OF ANY DAMAGE TO THESE LINES OR STRUCTURES.

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENTS SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS EMPLOYEES, AND AGENTS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE TO REPORT DISCREPANCIES IN PLANS AND/OR FIELD CONDITIONS IMMEDIATELY TO THE DESIGN ENGINEER FOR RESOLUTION PRIOR TO CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DISCREPANCIES NOT SO REPORTED AND RESOLVED.

**7 OAKS**  
 ENGINEERING  
 345 WESTFIELD ST. #107  
 SEASIDE, OR. 97138  
 503-738-1255  
 ADMIN@7OAKSENGINEERING.COM




NO	DATE	ISSUE DESCRIPTION

NO CHANGES, MODIFICATIONS OR REVISIONS TO BE MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.  
 DIMENSIONS AND NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.  
 THESE DRAWINGS MAY HAVE BEEN REPRODUCED AT A SIZE DIFFERENTLY THAN ORIGINALLY DRAWN. OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR USE OF INCORRECT SCALE.  
 CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO PROCEEDING WITH CONSTRUCTION AND NOTIFY ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES OR CONFLICTS.


PROJECT NAME:  
**MCLEOD SUBDIVISION**  
 PROJECT ADDRESS:  
**6255 MCLEOD**  
**KEIZER, OR.**

SHEET TITLE:  
**PRELIMINARY**  
**SUBDIVISION**  
**PLAN**

DATE:  
 02/20/2024  
 SHEET NUMBER:  
 4







**7 OAKS**  
ENGINEERING

345 WESTFIELD ST. #107  
SUNNYVALE, OR. 97381  
503.681.8455  
ADMIN@7OAKSENGINEERING.COM

STAMP:

REGISTERED PROFESSIONAL ENGINEER  
94115PE  
**PRELIMINARY**  
2021  
13  
KIMBERLY JOHNSON

NO	DATE	ISSUE DESCRIPTION

NO CHANGES, MODIFICATIONS OR REPRODUCTIONS TO BE MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.

DIMENSIONS AND NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.

THESE DRAWINGS MAY HAVE BEEN REPRODUCED AT A SIZE DIFFERENTLY THAN ORIGINALLY DRAWN; OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR USE OF INCORRECT SCALE.

CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO PROCEEDING WITH CONSTRUCTION AND NOTIFY ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES OR CONFLICTS.

QC BY:                      DRAWN BY:

PROJECT NAME:  
**MCLEOD SUBDIVISION**

PROJECT ADDRESS:  
**6255 MCLEOD**

**KEIZER, OR.**

SHEET TITLE:  
**STORMWATER PLAN**

DATE:  
02/20/2024

SHEET NUMBER:  
**6**

**NOTICE TO EXCAVATORS:**

ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.

(NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS

**Dig Safely.**

Call the Oregon One-Call Center  
DIAL 811 or 1-800-332-2344

**ENGINEER'S NOTICE TO CONTRACTOR:**

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITIES OR STRUCTURES SHOWN IN THESE PLANS ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS, AND TO THE BEST OF OUR KNOWLEDGE, THERE ARE NOT EXISTING UTILITIES EXCEPT THOSE SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE ALL PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN, AND ANY OTHER LINES OR STRUCTURES NOT SHOWN ON THESE PLANS, AND IS RESPONSIBLE FOR THE PROTECTION OF ANY DAMAGE TO THESE LINES OR STRUCTURES.

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENTS SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS EMPLOYEES, AND AGENTS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.


THE CONTRACTOR SHALL BE RESPONSIBLE TO REPORT DISCREPANCIES IN PLANS AND/OR FIELD CONDITIONS IMMEDIATELY TO THE DESIGN ENGINEER FOR RESOLUTION PRIOR TO CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DISCREPANCIES NOT SO REPORTED AND RESOLVED.

PRE VS. POST CONSTRUCTION FLOW RATES

FACILITY ID	PEAK FLOW RATE (CFS)											
	2-YEAR STORM		5 YEAR STORM		10 YEAR STORM		25 YEAR STORM		50 YEAR STORM		100 YEAR STORM	
PROJECT SITE	PRE	POST	PRE	POST	PRE	POST	PRE	POST	PRE	POST	PRE	POST
A	0.08	0.08	0.14	0.12	0.21	0.2	0.28	0.25	0.36	0.3	0.41	0.32

CATCHMENT AND FACILITY TABLE


CATCHMENT/ FACILITY ID	TOTAL AREA (SF)/(AC)	IMPERV/ US AREA (SF)	PERVIOUS AREA (SF)	OWNERSHIP (PRIVATE/ PUBLIC)	FACILITY TYPE	FACILITY SIZE
A	41,839	28,416	13,423	PRIVATE	Planter Strip Swale	1,500



**LEGEND:**

HYDROLOGY SUBAREA BOUNDARY LINE

DISTURBED AREA LABEL



**7 OAKS**  
ENGINEERING

345 WESTFIELD ST. #107  
 SEASIDE, OR. 97138  
 503.768.1855  
 ADMIN@7OAKSENGINEERING.COM

STAMP:



NO	DATE	ISSUE DESCRIPTION

NO CHANGES, MODIFICATIONS OR REPRODUCTIONS TO BE MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.  
 DIMENSIONS AND NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.  
 THESE DRAWINGS MAY HAVE BEEN REPRODUCED AT A SIZE DIFFERENTLY THAN ORIGINALLY DRAWN; OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR USE OF INCORRECT SCALE.  
 CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO PROCEEDING WITH CONSTRUCTION AND NOTIFY ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES OR CONFLICTS.

QC BY: \_\_\_\_\_ DRAWN BY: \_\_\_\_\_

PROJECT NAME:  
**MCLEOD SUBDIVISION**  
 PROJECT ADDRESS:  
**6255 MCLEOD**  
**KEIZER, OR.**

SHEET TITLE:  
**STORMWATER DETAILS**

DATE:  
 02/20/2024  
 SHEET NUMBER:  
**7**

**NOTICE TO EXCAVATORS:**  
 ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.  
 (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

**ENGINEER'S NOTICE TO CONTRACTOR:**

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITIES OR STRUCTURES SHOWN IN THESE PLANS ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS, AND TO THE BEST OF OUR KNOWLEDGE, THERE ARE NOT EXISTING UTILITIES EXCEPT THOSE SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE ALL PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN, AND ANY OTHER LINES OR STRUCTURES NOT SHOWN ON THESE PLANS, AND IS RESPONSIBLE FOR THE PROTECTION OF ANY DAMAGE TO THESE LINES OR STRUCTURES.

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENTS SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS EMPLOYEES, AND AGENTS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE TO REPORT DISCREPANCIES IN PLANS AND/OR FIELD CONDITIONS IMMEDIATELY TO THE DESIGN ENGINEER FOR RESOLUTION PRIOR TO CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DISCREPANCIES NOT SO REPORTED AND RESOLVED.

POTENTIAL UNDERGROUND FACILITY OWNERS  
**Dig Safely.**  
 Call the Oregon One-Call Center  
 DIAL 811 or 1-800-332-2344

APPENDIX D – GEOTECHNICAL REPORT



Real-World Geotechnical Solutions  
Investigation • Design • Construction Support

## Preliminary Geotechnical Engineering Report

<b>Project Information:</b>	McLeod Subdivision GeoPacific Project № 23-6474 January 16, 2024
<b>Site Location:</b>	6255 McLeod Lane Keizer, Oregon Marion County Tax Map 06 3W 36BB Lot 3700
<b>Client:</b>	Orreo LLC. P.O. Box 2717 Salem, Oregon 97308 Attn: Charles Weathers Email: orreoproperties@gmail.com

# TABLE OF CONTENTS

<b>1.0</b>	<b>PROJECT INFORMATION</b> .....	<b>1</b>
<b>2.0</b>	<b>SITE AND PROJECT DESCRIPTION</b> .....	<b>1</b>
<b>3.0</b>	<b>REGIONAL GEOLOGIC SETTING</b> .....	<b>1</b>
<b>4.0</b>	<b>REGIONAL SEISMIC SETTING</b> .....	<b>2</b>
4.1	Cascadia Subduction Zone .....	2
<b>5.0</b>	<b>FIELD EXPLORATION AND SUBSURFACE CONDITIONS</b> .....	<b>3</b>
5.1	Soil Descriptions .....	3
5.2	Shrink-Swell Potential .....	4
5.3	Groundwater and Soil Moisture .....	4
5.4	Infiltration Testing .....	4
<b>6.0</b>	<b>PRELIMINARY CONCLUSIONS AND RECOMMENDATIONS</b> .....	<b>5</b>
6.1	Site Preparation Recommendations .....	5
6.2	Engineered Fill .....	6
6.3	Excavating Conditions and Utility Trench Backfill .....	6
6.4	Erosion Control Considerations.....	7
6.5	Wet Weather Earthwork .....	7
6.6	Spread Foundations .....	8
6.7	Concrete Slabs-on-Grade .....	9
6.8	Footing and Roof Drains .....	10
<b>7.0</b>	<b>SEISMIC DESIGN</b> .....	<b>10</b>
7.1	Soil Liquefaction .....	11
<b>8.0</b>	<b>UNCERTAINTIES AND LIMITATIONS</b> .....	<b>12</b>
	<b>REFERENCES</b> .....	<b>13</b>

## APPENDIX

### List of Appendices

- Figures
- Exploration Logs
- Laboratory Results
- Photographic Log

### List of Figures

- A Excerpt of *Origin, extent, and thickness of Quaternary geologic units in the Willamette Valley, Oregon* (O'Connor et al., 2001)
- 1 Vicinity Map
- 2 Site Aerial and Exploration Locations



## **1.0 PROJECT INFORMATION**

This report presents the results of a preliminary geotechnical engineering study conducted by GeoPacific Engineering, Inc. (GeoPacific) for the above-referenced project. The purpose of our investigation was to evaluate subsurface conditions at the site, assess potential geologic hazards at the property, and to provide geotechnical recommendations for construction of an addition to the existing home. This geotechnical study was performed in accordance with GeoPacific Proposal № P-8601, dated October 20, 2023, and your subsequent authorization of our proposal and *General Conditions for Geotechnical Services*.

## **2.0 SITE AND PROJECT DESCRIPTION**

The subject site is located at 6255 McLeod Lane NE, in Keizer, Oregon, approximately 200 feet south of the intersection of Manzanita Street NE and McLeod Lane NE. The property is a rectangular residential neighborhood lot of approximately 2.48-acres in size and is identified as Lot 3700 on Marion County tax map 063W36BB. A residential home was located near the center of the site and was recently demolished. At the time of our investigation, we observed compacted gravel in the footprint of the previous home. Vegetation consists primarily of grass lawn and small to large trees. The site is bordered by McLeod Lane NE to the east and by residential lots in all other directions. Site topography relatively level, with elevations ranging from 158 to 160 feet above mean sea level (amsl). The site latitude and longitude are 45.010776, -123.007420, and the legal description is the NW ¼ of the NW ¼ of Section 36, T6S, R3E, Willamette Meridian.

GeoPacific understands that development at the site will include construction of a subdivision creating new building lots for residential homes, new local public streets, a stormwater retention facility and associated underground utilities. We expect the homes to be constructed with typical spread foundations incorporating continuous strip footings, and square column footings, with post and beam wood-framing above. A grading plan has not been provided for our review.

## **3.0 REGIONAL GEOLOGIC SETTING**

Regionally, the subject site lies within the Willamette Valley/Puget Sound lowland, a broad structural depression situated between the Coast Range on the west and the Cascade Range on the east. A series of discontinuous faults subdivide the Willamette Valley into a mosaic of fault-bounded, structural blocks (Yeats et al., 1996). Uplifted structural blocks form bedrock highlands, while down-warped structural blocks form sedimentary basins.

Geologic mapping indicates that the subject site is underlain by Quaternary age sediments (approximately 2.6 million years ago to present) of silt, sand, and gravel. The Quaternary sediments include alluvium and glaciofluvial sediment from the Cascade Range produced during Pleistocene glaciations (approximately 2.6 million to 12,000 years ago), and fine (Qff) and coarse (Qfc) grained catastrophic flood deposits. The catastrophic flood deposits were the result of repeated outburst of glacial Lake Missoula in western Montana approximately 15,000 to 13,000 years ago. The catastrophic floods transported sediments from western Washington to the Willamette Valley (Gannet and Caldwell, 1998; O'Conner et al., 2001). The catastrophic flood deposits in the

**Preliminary Geotechnical Engineering Report  
Project № 23-6474 McLeod Subdivision, Keizer, Oregon**

Willamette valley may be up to 100 feet in thickness and may display rhythmic bedding from several inches to several feet in thickness (O'Conner et al., 2001).

Soils to the west of the site are mapped as silt, sand, and gravel alluvium of the Willamette River (Qalc) and larger tributaries. To the north of the site lies the Lake Labish Ditch, a small tributary of the Willamette River, that is mapped with alluvium of smaller Willamette River tributaries (Qalf) (O'Conner et al., 2001). As shown on Figure A, below, geologic mapping by O'Conner et al. in 2001 differentiates the Missoula Flood deposits into a main body (Qff2) and a younger member (Qff1). The subject site is located in an area mapped as the younger member (Qff1). The younger member (Qff1) consists of catastrophic flood deposits that flank the Willamette River and its tributaries and possibly includes deposits of Qalf and Qalc.




Figure A - Excerpt of *Origin, extent, and thickness of Quaternary geologic units in the Willamette Valley, Oregon* (O'Connor et al., 2001). Site Location = ●

#### **4.0 REGIONAL SEISMIC SETTING**

According to the United States Geological Survey's Earthquake Hazards Program at least one major fault zone capable of generating damaging earthquakes is thought to exist in the vicinity of the subject site, the Cascadia Subduction Zone.

##### **4.1 Cascadia Subduction Zone**

The Cascadia Subduction Zone is a 680-mile-long zone of active tectonic convergence where oceanic crust of the Juan de Fuca Plate is subducting beneath the North American continent at a rate of 4 cm per year (Goldfinger et al., 1996). A growing body of geologic evidence suggests that prehistoric subduction zone earthquakes have occurred (Atwater, 1992; Carver, 1992; Peterson et al., 1993; Geomatrix Consultants, 1995). This evidence includes: (1) buried tidal marshes recording

episodic, sudden subsidence along the coast of northern California, Oregon, and Washington, (2) burial of subsided tidal marshes by tsunami wave deposits, (3) paleoliquefaction features, and (4) geodetic uplift patterns on the Oregon coast. Radiocarbon dates on buried tidal marshes indicate a recurrence interval for major subduction zone earthquakes of 250 to 650 years with the last event occurring 300 years ago (Atwater, 1992; Carver, 1992; Peterson et al., 1993; Geomatrix Consultants, 1995). The inferred seismogenic portion of the plate interface lies approximately along the Oregon Coast at depths of between 20 and 40 kilometers below the surface.

## **5.0 FIELD EXPLORATION AND SUBSURFACE CONDITIONS**

Our subsurface explorations for this report were conducted on November 27, 2023. A total of five exploratory test pits (TP-1 through TP-5) were excavated at the site to maximum depths of 10 feet below existing ground surface (bgs) using a medium sized track hoe. Explorations were conducted under the full-time observation of a GeoPacific geologist. During the explorations, pertinent information including soil sample depths, stratigraphy, soil engineering characteristics, and groundwater occurrence were recorded. At the completion of each test, the test pits were loosely backfilled with onsite soils. Soils were classified in accordance with the Unified Soil Classification System (USCS).

It should be noted that our explorations were located in the field by pacing or taping distances from apparent property corners and other site features shown on the plans provided. As such, the locations of the explorations should be considered approximate. Summary exploration logs are attached. The stratigraphic contacts shown on the individual test pit logs represent the approximate boundaries between soil types. The actual transitions may be more gradual. The soil and groundwater conditions depicted are only for the specific dates and locations reported, and therefore, are not necessarily representative of other locations and times. Soil and groundwater conditions encountered in the explorations are summarized in the following *Soil Descriptions* section.

### **5.1 Soil Descriptions**

**Topsoil:** At the ground surface of all of our test pit explorations, we encountered a soft, dark brown, organic SILT (OL) topsoil layer that was very moist and contained fine grass roots. The topsoil layer extends to approximately 8 to 12 inches beneath the surface, with up to 18 inches of topsoil in the vicinity of test pit TP-5 at the center of the site.

**Flood Deposits:** Beneath the topsoil in all of our test pit explorations, we found soft to medium stiff moist, light brown lean CLAY (CL) that was homogenous and plastic. At approximately 2 to 3 feet the lean CLAY (CL) transitions to a stiff to very stiff consistency, with black stained particles and faint bedding of fines. This material was interpreted to be catastrophic flood deposits from glacial Lake Missoula, possibly mixed with alluvium due to close proximity to the Willamette River flood plain. The flood deposits extended beyond the 10 feet maximum depth of our explorations onsite.

Laboratory testing conducted on a representative sample obtained from test pit TP-2 at a depth of 9 feet (elevation of infiltration testing) indicated approximately 88.4 percent by weight passing the U.S. No. 200 sieve, and a moisture content of 24.5 percent. Atterberg limit testing indicated a liquid limit

of 40, and a plasticity index of 18. The soil type is classified as lean CLAY (CL) according to the USCS soil classification system, and as A-6(168) according to AASHTO standards.

Laboratory testing conducted on a representative sample obtained from test pit TP-2 at a depth of 4 feet found approximately 90.7 percent by weight passing the U.S. No. 200 sieve, and a moisture content ranging from 22.5 percent. Laboratory testing conducted on a representative sample obtained from test pit TP-4 at a depth of 9 feet found approximately 89.1 percent by weight passing the U.S. No. 200 sieve, and a moisture content ranging from 24.3 percent.

**5.2 Shrink-Swell Potential**

Soft to very stiff, lean CLAY (CL) was encountered within our test pit explorations conducted at the site to depths of 10 feet. Based upon the results of our investigation and our local experience with the soil layers in the vicinity of the subject site, the plasticity of the soils is low, and the shrink-swell potential of the soil types is considered to be low. Special design measures are not considered necessary to minimize the risk of uncontrolled damage of foundations as a result of potential soil expansion at this site.

**5.3 Groundwater and Soil Moisture**

On November 27, 2023, observed soil moisture conditions were generally damp to moist. Groundwater seepage was not encountered within our test pit explorations to depths of 10 feet. Based on our review of available well logs from the *Oregon Water Resource Department, Groundwater information Mapping tool* (Oregon.gov, 2024), we understand that the depth to groundwater has been recorded at depths ranging from 15 to 30 feet bgs in the vicinity of the site. It is anticipated that groundwater conditions will vary depending on the season, local subsurface conditions, changes in site utilization, and other factors. Perched groundwater may be encountered in localized areas. Seeps and springs may exist in areas not explored and may become evident during site grading.

**5.4 Infiltration Testing**

Soil infiltration testing was performed using the encased falling-head method in test pit exploration TP-1 at depths of 4.5 and 6 feet bgs. The approximate locations of subsurface explorations are indicated in Figures 2 & 3. The water level was measured to the nearest 0.1 inch from a fixed point and the change in water level was recorded at regular intervals until three successive measurements showing a consistent infiltration rate were achieved. Table 1 summarizes the results of the encased falling-head infiltration tests. Infiltration rates have been reported without applying a factor of safety. Soils at the test locations were observed and sampled in order to characterize the subsurface profile.

**Table 1 - Summary of Infiltration Test Results**

Test Location	Depth (feet)	Soil Type	Infiltration Rate (in/hr)	Hydraulic Head Range (inches)
TP-2	4.5	Lean CLAY (CL)	0	14.5
TP-2	9	SILT (ML)	0.48	25.5-27

## **6.0 PRELIMINARY CONCLUSIONS AND RECOMMENDATIONS**

Our site investigation indicates that the proposed construction appears to be geotechnically feasible, provided that the recommendations of this report are incorporated into the design and construction phases of the project. The primary geotechnical concern associated with the site development is the presence of low permeability soils. Encased falling head infiltration testing was conducted in test pit exploration TP-2, in the northwest corner of the site. Measurable infiltration was not observed during the testing at a depth of 4.5 feet. Infiltration at a rate of approximately 0.48 inches per hour was observed in test pit TP-2 at a depth of 9 feet. Care should be taken in designing the storm water retention system.

Our geotechnical report is considered preliminary until we have reviewed a finalized grading plan for the project. GeoPacific may be contacted to revise the report once plans are available.

### **6.1 Site Preparation Recommendations**

Areas of proposed buildings, pavements, and areas to receive fill should be cleared of vegetation and any organic and inorganic debris. Existing structures should be demolished and any cavities structurally backfilled. Inorganic debris should be removed from the site. Organic materials from clearing should either be removed from the site or placed as landscape fill in areas not planned for structures. The final depth of soil removal will be determined on the basis of a site inspection after the stripping/excavation has been performed.

Organic-rich topsoil should then be stripped from construction areas of the site or where engineered fill is to be placed. The estimated average necessary depth of removal of moderately to highly organic soils is 8 to 12 inches. Deeper stripping to remove large tree roots or other organics may be necessary in localized areas. Organic soils were observed to a depth of approximately 18 inches in test pit TP-5, the exploration closest to the large trees at the center of the site. The final depth of soil removal will be determined on the basis of a site inspection after the stripping/excavation has been performed. Stripped topsoil should be stockpiled only in designated areas and stripping operations should be observed and documented by the geotechnical engineer or his representative.

In the influence zones of the proposed building and other settlement-sensitive structures, undocumented fills, buried topsoil, and subsurface structures (tile drains, basements, driveway and landscaping fill, old utility lines, cisterns, septic leach fields, etc.) should be removed and the excavations backfilled with engineered fill.

Exposed subgrade soils should be evaluated by the geotechnical engineer. For large areas, this evaluation is normally performed by proof-rolling the exposed subgrade with a fully loaded scraper or dump truck. For smaller areas where access is restricted, the subgrade should be evaluated by probing the soil with a steel probe. Soft/loose soils identified during subgrade preparation should be compacted to a firm and unyielding condition, over-excavated and replaced with engineered fill (as described below) or stabilized with rock prior to placement of engineered fill. The depth of over-excavation, if required, should be evaluated by the geotechnical engineer at the time of construction.

## **6.2 Engineered Fill**

All grading for the proposed construction should be performed as engineered grading in accordance with the applicable building code at the time of construction with the exceptions and additions noted herein. Areas proposed for fill placement should be prepared as described in the Site Preparation Recommendations section. Surface soils should then be scarified and recompacted prior to placement of structural fill. Proper test frequency and earthwork documentation usually requires daily observation and testing during stripping, rough grading, and placement of engineered fill. Imported fill material must be approved by the geotechnical engineer prior to being imported to the site. Oversize material greater than 6 inches in size should not be used within 3 feet of foundation footings, and material greater than 12 inches in diameter should not be used in engineered fill.

Engineered fill should be compacted in horizontal lifts not exceeding 12 inches using standard compaction equipment. We recommend that engineered fill be compacted to at least 95 percent of the maximum dry density determined by ASTM D698 (Standard Proctor) or equivalent. Soils should be moisture conditioned to within two percent of optimum moisture. Field density testing should conform to ASTM D2922 and D3017, or D1556. All engineered fill should be observed and tested by the project geotechnical engineer or his representative. Typically, one density test is performed for at least every 2 vertical feet of fill placed or every 500 yd<sup>3</sup>, whichever requires more testing. Because testing is performed on an on-call basis, we recommend that the earthwork contractor be held contractually responsible for test scheduling and frequency.

Site earthwork may be impacted by perched groundwater, soil moisture and wet weather conditions. Earthwork in wet weather would likely require extensive use of additional crushed aggregate, cement or lime treatment, or other special measures, at considerable additional cost compared to earthwork performed under dry-weather conditions.

## **6.3 Excavating Conditions and Utility Trench Backfill**

We anticipate that onsite soils can generally be excavated using conventional heavy equipment. These deposits are not cohesive and may exhibit sidewall collapse during deep trenching. Maintenance of safe working conditions, including temporary excavation stability, is the responsibility of the contractor. Actual slope inclinations at the time of construction should be determined based on safety requirements and actual soil and groundwater conditions. All temporary cuts in excess of 4 feet in height should be sloped in accordance with U.S. Occupational Safety and Health Administration (OSHA) regulations (29 CFR Part 1926) or be shored. The native clay and silt soils classify as Type B Soil and temporary excavation side slope inclinations as steep as 1H:1V may be assumed for planning purposes. These cut slope inclinations are applicable to excavations above the water table only, where seepage is not encountered.

Vibrations created by traffic and construction equipment may cause some caving and raveling of excavation walls. In such an event, lateral support for the excavation walls should be provided by the contractor to prevent loss of ground support and possible distress to existing or previously constructed structural improvements.

**Preliminary Geotechnical Engineering Report  
Project № 23-6474 McLeod Subdivision, Keizer, Oregon**

Underground utility pipes should be installed in accordance with the procedures specified in ASTM D2321 and applicable city and county standards. We recommend that structural trench backfill be compacted to at least 95 percent of the maximum dry density obtained by the Standard Proctor (ASTM D698, AASHTO T-99) or equivalent. Initial backfill lift thicknesses for a  $\frac{3}{4}$ "-0 crushed aggregate base may need to be as great as 4 feet to reduce the risk of flattening underlying flexible pipe. Subsequent lift thickness should not exceed 1 foot. If imported granular fill material is used, then the lifts for large vibrating plate-compaction equipment (e.g. hoe compactor attachments) may be up to 2 feet, provided that proper compaction is being achieved and each lift is tested. Use of large vibrating compaction equipment should be carefully monitored near existing structures and improvements due to the potential for vibration-induced damage.

Adequate density testing should be performed during construction to verify that the recommended relative compaction is achieved. Typically, at least one density test is taken for every 4 vertical feet of backfill on each 100-lineal-foot section of trench.

#### **6.4 Erosion Control Considerations**

During our field exploration program, we did not observe soil and topographic conditions which are considered highly susceptible to erosion. In our opinion, the primary concern regarding erosion potential will occur during construction in areas that have been stripped of vegetation. Erosion at the site during construction can be minimized by implementing the project erosion control plan, which should include judicious use of straw wattles, fiber rolls, and silt fences. If used, these erosion control devices should remain in place throughout site preparation and construction.

Erosion and sedimentation of exposed soils can also be minimized by quickly re-vegetating exposed areas of soil, and by staging construction such that large areas of the project site are not denuded and exposed at the same time. Areas of exposed soil requiring immediate and/or temporary protection against exposure should be covered with either mulch or erosion control netting/blankets. Areas of exposed soil requiring permanent stabilization should be seeded with an approved grass seed mixture, or hydroseeded with an approved seed-mulch-fertilizer mixture.

#### **6.5 Wet Weather Earthwork**

Soils underlying the site are likely to be moisture sensitive and will be difficult to handle or traverse with construction equipment during periods of wet weather. Earthwork is typically most economical when performed under dry weather conditions. Earthwork performed during the wet-weather season will require expensive measures such as cement treatment or imported granular material to compact areas where fill may be proposed to the recommended engineering specifications. If earthwork is to be performed or fill is to be placed in wet weather or under wet conditions when soil moisture content is difficult to control, the following recommendations should be incorporated into the contract specifications.

- Earthwork should be performed in small areas to minimize exposure to wet weather. Excavation or the removal of unsuitable soils should be followed promptly by the placement and compaction of clean engineered fill. The size and type of construction equipment used

**Preliminary Geotechnical Engineering Report**  
**Project № 23-6474 McLeod Subdivision, Keizer, Oregon**

may have to be limited to prevent soil disturbance. Under some circumstances, it may be necessary to excavate soils with a backhoe to minimize subgrade disturbance caused by equipment traffic;

- The ground surface within the construction area should be graded to promote run-off of surface water and to prevent the ponding of water;
- Material used as engineered fill should consist of clean, granular soil containing less than 5 percent passing the No. 200 sieve. The fines should be non-plastic. Alternatively, cement treatment of on-site soils may be performed to facilitate wet weather placement;
- The ground surface within the construction area should be sealed by a smooth drum vibratory roller, or equivalent, and under no circumstances should be left uncompacted and exposed to moisture. Soils which become too wet for compaction should be removed and replaced with clean granular materials;
- Excavation and placement of fill should be observed by the geotechnical engineer to verify that all unsuitable materials are removed and suitable compaction and site drainage is achieved; and
- Geotextile silt fences, straw wattles, and fiber rolls should be strategically located to control erosion.

If cement or lime treatment is used to facilitate wet weather construction, GeoPacific should be contacted to provide additional recommendations and field monitoring.

## **6.6 Spread Foundations**

A grading plan for the project has not been provided at this time. However, based on communication with the client, we anticipate cut and fill on the order of 6 feet or less. The proposed residential homes will likely be constructed on typical spread foundations with square column footings, continuous strip footings, and crawl spaces. We anticipate wood-framed construction above the foundations with maximum structural loading on column footings and continuous strip footings on the order of 10 to 35 kips, and 2 to 7 kips respectively.

Residential structures may be supported on shallow foundations bearing on competent undisturbed, native soils and/or engineered fill, appropriately designed and constructed as recommended in this report. Areas where homes are to be constructed where no engineered fill will be placed should either be prepared as recommended for roadway areas; or the foundation envelopes of the proposed homes should be over-excavated to expose native soils on a lot-by-lot basis (see *Site Preparation Recommendations* section).

Foundation design, construction, and setback requirements should conform to the applicable building code at the time of construction. For maximization of bearing strength and protection against frost heave, spread footings should be embedded at a minimum depth of 12 inches below exterior grade except where footing-to-slope setbacks require deeper embedment. The recommended minimum widths for continuous footings supporting wood-framed walls without masonry are 12 inches for single-story, 15 inches for two-story, and 18 inches for three-story structures. Minimum



**Preliminary Geotechnical Engineering Report**  
**Project № 23-6474 McLeod Subdivision, Keizer, Oregon**

foundation reinforcement should consist of a No. 4 bar at the top of stem walls, and a No. 4 bar at the bottom of the footings. Concrete slab-on-grade reinforcement should consist of No. 4 bars placed on 24-inch centers in a grid pattern.

The anticipated allowable soil bearing pressure is 1,500 lbs/ft<sup>2</sup> for footings bearing on competent, low expansivity, native soil and/or engineered fill. A maximum chimney and column load of 40 kips is recommended for the site. The recommended maximum allowable bearing pressure may be increased by 1/3 for short-term transient conditions such as wind and seismic loading. For heavier loads, the geotechnical engineer should be consulted. The coefficient of friction between on-site soil and poured-in-place concrete may be taken as 0.42, which includes no factor of safety. The maximum anticipated total and differential footing movements (generally from soil expansion and/or settlement) are 1 inch and ¾ inch over a span of 20 feet, respectively. We anticipate that the majority of the estimated settlement will occur during construction, as loads are applied. Excavations near structural footings should not extend within a 1H:1V plane projected downward from the bottom edge of footings.

Footing excavations should penetrate through topsoil, undocumented fill, and any loose soil to competent subgrade that is suitable for bearing support. All footing excavations should be trimmed neat, and all loose or softened soil should be removed from the excavation bottom prior to placing reinforcing steel bars. Due to the moisture sensitivity of on-site native soils, foundations constructed during the wet weather season may require over-excavation of footings and backfill with compacted, crushed aggregate.

Our recommendations are for house construction incorporating raised wood floors and conventional spread footing foundations. If living space of the structures incorporate basements, a geotechnical engineer should be consulted to make additional recommendations for retaining walls, waterproofing, underslab drainage and wall subdrains. After site development, a Final Soil Engineer's Report should either confirm or modify the above recommendations.

## **6.7 Concrete Slabs-on-Grade**

Preparation of areas beneath concrete slab-on-grade floors should be performed as described in the *Site Preparation Recommendations* and *Spread Foundations* sections of this report. Care should be taken during excavation for foundations and floor slabs, to avoid disturbing subgrade soils. If subgrade soils have been adversely impacted by wet weather or otherwise disturbed, the surficial soils should be scarified to a minimum depth of 8 inches, moisture conditioned to within about 3 percent of optimum moisture content and compacted to engineered fill specifications. Alternatively, disturbed soils may be removed, and the removal zone backfilled with additional crushed rock.

For evaluation of the concrete slab-on-grade floors using the beam on elastic foundation method, a modulus of subgrade reaction of 150 kcf (87 pci) should be assumed for the stiff, fine -grained soils anticipated to be present at foundation subgrade elevation following adequate site preparation as described above. This value assumes the concrete slab system is designed and constructed as recommended herein, with a minimum thickness of 8 inches of 1½"-0 crushed aggregate beneath the slab. The total thickness of crushed aggregate will be dependent on the subgrade conditions at

**Preliminary Geotechnical Engineering Report  
Project № 23-6474 McLeod Subdivision, Keizer, Oregon**

the time of construction and should be verified visually by proof-rolling. Under-slab aggregate should be compacted to at least 95 percent of its maximum dry density as determined by ASTM D698 (Standard Proctor) or equivalent.

In areas where moisture will be detrimental to floor coverings or equipment inside the proposed structure, appropriate vapor barrier and damp-proofing measures should be implemented. Appropriate design professionals should be consulted regarding vapor barrier and damp proofing systems, ventilation, building material selection and mold prevention issues, which are outside GeoPacific's area of expertise.

## **6.8 Footing and Roof Drains**

The outside edge of perimeter footings should be provided with a drainage system consisting of 3-inch diameter, slotted, flexible plastic pipe embedded in a minimum of 1 ft<sup>3</sup> per lineal foot of clean, free-draining gravel or 1 1/2" - 3/4" drain rock. The drain pipe and surrounding drain rock should be wrapped in non-woven geotextile (Mirafi 140N, or approved equivalent) to minimize the potential for clogging and/or ground loss due to piping. Water collected from the footing drains should be directed into the local storm drain system or other suitable outlet. A minimum 0.5 percent fall should be maintained throughout the drain and non-perforated pipe outlet. Down spouts and roof drains should not be connected to the foundation drains in order to reduce the potential for clogging. The footing drains should include clean-outs to allow periodic maintenance and inspection. Grades around the proposed structure should be sloped such that surface water drains away from the building.

Footing drains are recommended to prevent detrimental effects of surface water runoff on foundations – not to dewater groundwater. Footing drains should not be expected to eliminate all potential sources of water entering a basement or beneath a slab-on-grade. An adequate grade to a low point outlet drain in the crawlspace, if utilized, is required by code.

## **7.0 SEISMIC DESIGN**

The Oregon Department of Geology and Mineral Industries (DOGAMI), Oregon HazVu: 2023 Statewide GeoHazards Viewer indicates that the site is in an area where severe ground shaking is anticipated during an earthquake. Structures should be designed to resist earthquake loading in accordance with the methodology described in the 2021 International Building Code (IBC) with applicable Oregon Structural Specialty Code (OSSC) revisions (current 2022). We recommend Site Class D be used for design as defined in ASCE 7-16, Chapter 20, and Table 20.3-1. Design values determined for the site using the ATC Hazards by Location 2023 Seismic Design Maps Summary Report are summarized in Table 2 and are based upon observed existing soil conditions.

**Table 2 - Recommended Earthquake Ground Motion Parameters (ASCE-7-16)**

Parameter	Value
Location (Lat, Long), degrees	45.0170259, -123.0073176
Risk-Targeted Maximum Considered Earthquake Design Parameters, 2% Exceedance in 50 years (MCE <sub>R</sub> ):	
Site Modified Peak Ground Acceleration PGA <sub>M</sub>	0.466 g
Short Period, S <sub>s</sub>	0.826 g
1.0 Sec Period, S <sub>1</sub>	0.410 g
Soil Factors for Site Class D:	
F <sub>a</sub>	1.170
* F <sub>v</sub>	1.890
SD <sub>s</sub> = 2/3 x F <sub>a</sub> x S <sub>s</sub>	0.644 g
*SD <sub>1</sub> = 2/3 x F <sub>v</sub> x S <sub>1</sub>	0.516 g
Seismic Design Category	D (D <sub>0</sub> per 2021 IRC)

\* F<sub>v</sub> value reported in the above table is a straight-line interpolation of mapped spectral response acceleration at 1-second period, S<sub>1</sub> per Table 1613.2.3(2) of OSSC 2019 with the assumption that Exception 2 of ASCE 7-16 Chapter 11.4.8 is met per the Structural Engineer. If Exception 2 is not met, and the long-period site coefficient (F<sub>v</sub>) is required for design, GeoPacific Engineering can be consulted to provide a site-specific procedure as per ASCE 7-16, Chapter 21.

## 7.1 Soil Liquefaction

The Oregon Department of Geology and Mineral Industries (DOGAMI), Oregon HazVu: 2023 Statewide GeoHazards Viewer indicates that the site is mapped as being at a *low* risk of soil liquefaction during an earthquake. Soil liquefaction is a phenomenon wherein saturated soil deposits temporarily lose strength and behave as a liquid in response to ground shaking caused by strong earthquakes. Soil liquefaction is generally limited to loose sands and granular soils located below the water table, and fine-grained soils with a plasticity index less than 15. The subsurface profile observed within our explorations and our experience with geologic conditions in the site vicinity indicate that the site is underlain by soft to very stiff clay flood deposits. Based on available well log data, static groundwater is expected to be present at depths of 15 to 30 feet bgs in the vicinity of the site. Based on the results of our subsurface investigation and our understanding of the geologic conditions in the site vicinity, it is our opinion that the risk of liquefaction on the site is low.

For construction of single family structures, special design or construction measures are not required by code to mitigate the effects of liquefaction. An in-depth analysis of seismic hazards is beyond the scope of this study. However, if additional information is desired regarding the potential for soil liquefaction during a seismic event, GeoPacific may be consulted to perform additional subsurface explorations, consisting of soil borings and/or CPT testing, and to perform a quantitative liquefaction analysis. If multi-family residential, high occupancy, or critical structures were to be incorporated into plans for site development, further study and evaluation of seismic hazards would be required by code to more fully evaluate the potential adverse effects due to liquefaction, such as vertical settlement, lateral deformation, and lateral spreading.

### **8.0 UNCERTAINTIES AND LIMITATIONS**

We have prepared this report for the owner and their consultants for use in design of this project only. This report should be provided in its entirety to prospective contractors for bidding and estimating purposes; however, the conclusions and interpretations presented in this report should not be construed as a warranty of the subsurface conditions. Experience has shown that soil and groundwater conditions can vary significantly over small distances. Inconsistent conditions can occur between explorations that may not be detected by a geotechnical study. If, during future site operations, subsurface conditions are encountered which vary appreciably from those described herein, GeoPacific should be notified for review of the recommendations of this report, and revision of such if necessary.


Sufficient geotechnical monitoring, testing and consultation should be provided during construction to confirm that the conditions encountered are consistent with those indicated by explorations. The checklist attached to this report outlines recommended geotechnical observations and testing for the project. Recommendations for design changes will be provided should conditions revealed during construction differ from those anticipated, and to verify that the geotechnical aspects of construction comply with the contract plans and specifications.

Within the limitations of scope, schedule and budget, GeoPacific attempted to execute these services in accordance with generally accepted professional principles and practices in the fields of geotechnical engineering and engineering geology at the time the report was prepared. No warranty, expressed or implied, is made. The scope of our work did not include environmental assessments or evaluations regarding the presence or absence of wetlands or hazardous or toxic substances in the soil, surface water, or groundwater at this site.


We appreciate this opportunity to be of service.

Sincerely,

**GEOPACIFIC ENGINEERING, INC.**



Michael T. Baker, R.G.  
Staff Geologist



Benjamin G. Anderson, P.E.  
Associate Engineer

## **REFERENCES**

- ATC Hazards by Location, (<https://hazards.atcouncil.org>).
- Atwater, B.F., 1992, Geologic evidence for earthquakes during the past 2,000 years along the Copalis River, southern coastal Washington: *Journal of Geophysical Research*, v. 97, p. 1901-1919.
- Carver, G.A., 1992, Late Cenozoic tectonics of coastal northern California: *American Association of Petroleum Geologists-SEPM Field Trip Guidebook*, 1992.
- Gannet, Marshall W., and Caldwell, Rodney R., *Generalized Geologic Map of the Willamette Lowland*, U.S. Department of the interior, U.S. Geological Survey, 1998.
- Goldfinger, C., Kulm, L.D., Yeats, R.S., Appelgate, B, MacKay, M.E., and Cochrane, G.R., 1996, Active strike-slip faulting and folding of the Cascadia Subduction-Zone plate boundary and forearc in central and northern Oregon: in *Assessing earthquake hazards and reducing risk in the Pacific Northwest*, v. 1: U.S. Geological Survey Professional Paper 1560, p. 223-256
- Geomatrix Consultants, 1995, *Seismic Design Mapping, State of Oregon*: unpublished report prepared for Oregon Department of Transportation, Personal Services Contract 11688, January 1995.
- O'Connor, J.E., Sarna-Wojcicki, A., Wozniak, K.C., Polette, D.J., and Fleck, R.J., 2001, Origin, extent, and thickness of Quaternary geologic units in the Willamette Valley, Oregon: U.S. Geological Survey, Professional Paper 1620, scale 1:250,000.
- Oregon Department of Geology and Mineral Industries, *Statewide Geohazards Viewer*, [www.oregongeology.org/hazvu](http://www.oregongeology.org/hazvu), 2023.
- Oregon Water Resources Department, 2023, Well Report Query: [https://apps.wrd.state.or.us/apps/gw/well\\_log/](https://apps.wrd.state.or.us/apps/gw/well_log/)
- Peterson, C.D., Darionzo, M.E., Burns, S.F., and Burris, W.K., 1993, Field trip guide to Cascadia paleoseismic evidence along the northern California coast: evidence of subduction zone seismicity in the central Cascadia margin: *Oregon Geology*, v. 55, p. 99-144.
- United States Geological Survey, *USGS Earthquake Hazards Program Website* ([earthquake.usgs.gov](http://earthquake.usgs.gov)), 2023.
- Yeats, R.S., Graven, E.P., Werner, K.S., Goldfinger, C., and Popowski, T., 1996, Tectonics of the Willamette Valley, Oregon: in *Assessing earthquake hazards and reducing risk in the Pacific Northwest*, v. 1: U.S. Geological Survey Professional Paper 1560, P. 183-222, 5 plates, scale 1:100,000.

**Preliminary Geotechnical Engineering Report  
Project № 23-6474 McLeod Subdivision, Keizer, Oregon**


**CHECKLIST OF RECOMMENDED GEOTECHNICAL TESTING AND OBSERVATION**

<b>Item No.</b>	<b>Procedure</b>	<b>Timing</b>	<b>By Whom</b>	<b>Done</b>
1	Preconstruction meeting	Prior to beginning site work	Contractor, Developer, Civil and Geotechnical Engineers	
2	Fill removal from site or sorting and stockpiling	Prior to mass stripping	Soil Technician/ Geotechnical Engineer	
3	Stripping, aeration, and root-picking operations	During stripping	Soil Technician	
4	Compaction testing of engineered fill (95% of Standard Proctor)	During filling, tested every 2 vertical feet	Soil Technician	
5	Foundation Subgrade Compaction (95% of Modified Proctor)	During Foundation Preparation, Prior to Placement of Reinforcing Steel	Soil Technician/ Geotechnical Engineer	
6	Compaction testing of trench backfill (95% of Standard Proctor)	During backfilling, tested every 4 vertical feet for every 200 linear feet	Soil Technician	
7	Street Subgrade Inspection (95% of Standard Proctor or Equivalent)	Prior to placing base course	Soil Technician	
8	Base course compaction (95% of Modified Proctor)	Prior to paving, tested every 200 linear feet	Soil Technician	
9	Asphalt Compaction (92% Rice Value)	During paving, tested every 100 linear feet	Soil Technician	
10	Final Geotechnical Engineer's Report	Completion of project	Geotechnical Engineer	

**Real-World Geotechnical Solutions**  
**Investigation • Design • Construction Support**



## **FIGURES**



### Legend

Approximate Scale 1 in = 2,000 ft

Drawn by: MTB  
 Date: 12.8.2023

Base maps:

U.S. Geological Survey 7.5 minute Topographic Map Series,  
 Mission Bottom, Gervais & Salem East, Oregon Quadrangle, 2020  
 and Salem West, Oregon Quadrangle, 2023.



Project: McLeod Subdivision  
 Keizer, Oregon

Project No. 23-6474

FIGURE 1





Base image provided by Marion County Assessor's Office


**Legend**



Test Pit Designation and  
Approximate Location



Site Boundary



Drawn by: MTB  
Date: 12.8.2023

Project: McLeod Subdivision  
Keizer, Oregon

Project No. 23-6474

FIGURE 2

**Real-World Geotechnical Solutions**  
**Investigation • Design • Construction Support**



## **EXPLORATION LOGS**

Project: Mcleod Subdivision  
Keizer, Oregon

Project No. 23-6474

Exploration No. **TP-1**

Depth (ft)	Sample Type	tons/sq.ft.	Moisture Content (%)	Water Bearing Zone	Material Description
1		1.0			Organic SILT (OL), dark brown, fine roots, soft, moist [Topsoil]
2		1.5			Lean CLAY (CL), light brown, subtle orange and gray mottling, low to moderate plasticity, homogenous, moist, soft to medium stiff [Flood Deposits]
3		3.5			Grades to light brown to tan, faint gray mottling, low to moderate plasticity, homogenous, blocky, micaceous, black stained particles, faint bedding of varying fines concentration, damp to moist, stiff [Flood Deposits]
4		3.0			
5					
6					
7					
8					
9					
10					
11					Exploration terminated at 10 feet. Groundwater not encountered.

### LEGEND



Bag Sample



Split-Spoon



Shelby Tube Sample



Seepage



Static Water Table





Water Bearing Zone

Date Excavated: 11.27.2023  
Logged By: MTB  
Surface Elevation: 159 Feet

Project: Mcleod Subdivision  
 Keizer, Oregon

Project No. 23-6474

Exploration No. **TP-2**

Depth (ft)	Sample Type	tons/sq.ft.	Moisture Content (%)	Water Bearing Zone	Material Description
					Organic SILT (OL), dark brown, fine roots, soft, moist [Topsoil]
1		1.0			Lean CLAY (CL), brown, subtle orange and gray mottling, low to moderate plasticity, homogenous, moist, soft to medium stiff [Flood Deposits]
2		2.0			
3		4.0			Grades to light brown to tan, subtle orange and gray gray mottling, low to moderate plasticity, faint bedding of varying fines concentration, blocky, micaceous, black stained particles, damp to moist, stiff [Flood Deposits]
4		4.5			
5			22.5		[Percent passing the # 200 sieve = 90.7 percent]
6					
7					
8					
9			24.5		[Percent passing the # 200 sieve = 88.4 percent]
10					
11					Exploration terminated at 10 feet. Groundwater not encountered.

LEGEND



Bag Sample



Split-Spoon



Shelby Tube Sample



Seepage



Static Water Table



Water Bearing Zone

Date Excavated: 11.27.2023  
 Logged By: MTB  
 Surface Elevation: 160 Feet

Project: Mcleod Subdivision  
Keizer, Oregon

Project No. 23-6474

Exploration No. **TP-3**

Depth (ft)	Sample Type	tons/sq.ft.	Moisture Content (%)	Water Bearing Zone	Material Description
1		1.0			Organic SILT (OL), dark brown, fine roots, soft, moist [Topsoil]
2		1.0			Lean CLAY (CL), light brown, subtle orange and gray mottling, low to moderate plasticity, homogenous, moist, soft to medium stiff [Flood Deposits]
3		4.0			
4		4.5			Grades to light brown to tan, faint gray mottling, low to moderate plasticity, homogenous, blocky, micaceous, black stained particles, faint bedding of varying fines concentration, damp to moist, stiff [Flood Deposits]
5					
6					
7					
8					
9					
10					
11					Exploration terminated at 10 feet. Groundwater not encountered.

LEGEND



Bag Sample



Split-Spoon



Shelby Tube Sample



Seepage



Static Water Table




Water Bearing Zone

Date Excavated: 11.27.2023  
Logged By: MTB  
Surface Elevation: 159 Feet

Project: Mcleod Subdivision  
Keizer, Oregon

Project No. 23-6474

Exploration No. **TP-4**

Depth (ft)	Sample Type	tons/sq.ft.	Moisture Content (%)	Water Bearing Zone	Material Description
1		1.5			Organic SILT (OL) with gravel, dark brown, fine roots, concrete fragments, soft, moist [Topsoil/Fill]
2		4.5			Lean CLAY (CL), light brown, subtle orange and gray mottling, low to moderate plasticity, homogenous, moist, soft to medium stiff [Flood Deposits]
3		3.5			Grades to light brown to tan, faint gray mottling, low to moderate plasticity, homogenous, blocky, micaceous, black stained particles, faint bedding of varying fines concentration, damp to moist, stiff [Flood Deposits]
4		4.0			
5					
6					
7					
8					
9			24.3		[Percent passing the # 200 sieve = 89.1 percent]
10					Exploration terminated at 10 feet. Groundwater not encountered.
11					

LEGEND



Bag Sample



Split-Spoon



Shelby Tube Sample



Seepage



Static Water Table



Water Bearing Zone

Date Excavated: 11.27.2023  
Logged By: MTB  
Surface Elevation: 160 Feet

Project: Mcleod Subdivision  
Keizer, Oregon

Project No. 23-6474

Exploration No. **TP-5**

Depth (ft)	Sample Type	tons/sq.ft.	Moisture Content (%)	Water Bearing Zone	Material Description
1		1.5			Organic SILT (OL), dark brown, numerous tree roots, soft, moist [Topsoil]
2		4.0			Lean CLAY (CL), light brown, subtle orange and gray mottling, low to moderate plasticity, homogenous, moist, soft to medium stiff [Flood Deposits]
3		4.5			Grades to light brown to tan, faint gray mottling, low to moderate plasticity, homogenous, blocky, micaceous, black stained particles, faint bedding of varying fines concentration, damp to moist, stiff [Flood Deposits]
4		4.5			
5					
6					
7					
8					
9					
10					
11					Exploration terminated at 10 feet. Groundwater not encountered.

LEGEND



Bag Sample



Split-Spoon



Shelby Tube Sample



Seepage



Static Water Table



Water Bearing Zone

Date Excavated: 11.27.2023  
Logged By: MTB  
Surface Elevation: 159 Feet

**Real-World Geotechnical Solutions**  
**Investigation • Design • Construction Support**



## **LABORATORY RESULTS**



Project Name: Mcleod Subdivision  
 Date Sampled: 11.27.2023  
 Sampled By: MTB

Project #: 23-6474  
 Date Tested: 11.28.2023  
 Tested By: MTB/DPM

**Moisture Content**

<b>Sample ID:</b>	<b>S23-221</b>
Exploration & Depth:	<b>TP-2 4ft</b>
Tare #:	53
Tare (g):	156.1
Tare + Wet (g):	700.7
Tare + Dry (g):	600.7
Moisture (%):	22.5

**#200 Wet Sieve**

<b>Sample ID:</b>	<b>S23-221</b>
Exploration & Depth:	<b>TP-2 4ft</b>
Tare #:	53
Tare (g):	156.1
Tare + Prewash (g):	600.7
Tare + Washed (g):	197.5
Passing #200 (%):	90.7

**Moisture Content**

<b>Sample ID:</b>	<b>S23-223</b>
Exploration & Depth:	<b>TP-4 9ft</b>
Tare #:	50
Tare (g):	156.7
Tare + Wet (g):	605.0
Tare + Dry (g):	517.3
Moisture (%):	24.3

**#200 Wet Sieve**

<b>Sample ID:</b>	<b>S23-223</b>
Exploration & Depth:	<b>TP-4 9ft</b>
Tare #:	50
Tare (g):	156.7
Tare + Prewash (g):	517.3
Tare + Washed (g):	195.9
Passing #200 (%):	89.1

**Moisture Content**

<b>Sample ID:</b>	
Exploration & Depth:	
Tare #:	
Tare (g):	
Tare + Wet (g):	
Tare + Dry (g):	
Moisture (%):	#DIV/0!

**#200 Wet Sieve**

<b>Sample ID:</b>	
Exploration & Depth:	
Tare #:	
Tare (g):	
Tare + Prewash (g):	
Tare + Washed (g):	
Passing #200 (%):	#DIV/0!


**Moisture Content**

<b>Sample ID:</b>	
Exploration & Depth:	
Tare #:	
Tare (g):	
Tare + Wet (g):	
Tare + Dry (g):	
Moisture (%):	#DIV/0!

**#200 Wet Sieve**

<b>Sample ID:</b>	
Exploration & Depth:	
Tare #:	
Tare (g):	
Tare + Prewash (g):	
Tare + Washed (g):	
Passing #200 (%):	#DIV/0!

# Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.0	1.2	10.4	88.4	

TEST RESULTS			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
.75	100.0		
.5	100.0		
.375	100.0		
.25	100.0		
#4	100.0		
#10	100.0		
#20	99.5		
#40	98.8		
#60	98.3		
#100	97.7		
#200	88.4		

**Material Description**

Lean CLAY

**Atterberg Limits (ASTM D 4318)**

PL= 22                      LL= 40                      PI= 18

**Classification**

USCS (D 2487)= CL                      AASHTO (M 145)= A-6(16)

**Coefficients**

D<sub>90</sub>= 0.0824                      D<sub>85</sub>=                      D<sub>60</sub>=  
D<sub>50</sub>=                      D<sub>30</sub>=                      D<sub>15</sub>=  
D<sub>10</sub>=                      C<sub>u</sub>=                      C<sub>c</sub>=

**Remarks**

Moisture Content = 24.5 percent

---

Date Received: \_\_\_\_\_ Date Tested: 11.28.2023

Tested By: DPM/MTB

Checked By: \_\_\_\_\_



Title: \_\_\_\_\_

\* (no specification provided)

Location: TP-2                      Sample Number: S23-222                      Depth: 9ft                      Date Sampled: 11.27.2023

<h2 style="margin: 0;">GEOPACIFIC ENGINEERING, INC.</h2>	<p>Client: Oreo LLC  Project: Mcleod Subdivision  Project No: 23-6474</p>
--	---

# LIQUID AND PLASTIC LIMITS TEST REPORT



MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
Lean CLAY	40	22	18	98.8	88.4	CL

Project No. 23-6474      Client: Oreo LLC  
 Project: Mcleod Subdivision  
 Location: TP-2  
 Sample Number: S23-222      Depth: 9ft

Remarks:

## GEOPACIFIC ENGINEERING, INC.

Figure

Tested By: DPM/MTB

**Real-World Geotechnical Solutions**  
**Investigation • Design • Construction Support**



## **PHOTOGRAPHIC LOG**



Real-World Geotechnical Solutions  
Investigation • Design • Construction Support




**Test Pit TP-1**





Real-World Geotechnical Solutions  
Investigation • Design • Construction Support



**Test Pit TP-2**





Real-World Geotechnical Solutions  
Investigation • Design • Construction Support



**Test Pit TP-3**





Real-World Geotechnical Solutions  
Investigation • Design • Construction Support



**Test Pit TP-4**







Real-World Geotechnical Solutions  
Investigation • Design • Construction Support



**Test Pit TP-5**

